RAYTAC abietec
勁達國際電子股份有限公司 Raytac Corp
艾碧科技股份有限公司 abietec Inc

Version: 1.2
Issued Date: 2026/09/09

Data Sheet

(規格書)

產品名稱	(Product)	Bluetooth Low Energy Module
解決方案	(Solution)	Nordic nRF54L15 / nRF54L10 / nRF54L05
		QFN Package
產品型號	(Model No.)	**AN54LQ-U15 / AN54LQ-U10 / AN54LQ-U05**
		(u.FL Antenna)
產品料號	(Part No.)	See *4.3 Order code*

Model	Working distance (in Meters) 125 Kbps	1 Mbps	2 Mbps	Operating Temperature
AN54LQ-15 / 10 / 05	over 750	over 400	over 300	-40 ~ 105℃
AN54LQ-P15 / P10 / P05	over 450	up to 250	up to 200	-40 ~ 105℃
AN54LQ-U15 / U10 / U05	over 750	up to 400	up to 300	-40 ~ 85℃

Working range is tested in open space

Index

1. Overall introduction 4
1.1. Application 4
1.2. Features 5

2. Product dimension 6
2.1. PCB dimensions & pin Indication 6
2.2. Recommended layout of solder pad 7
2.3. RF layout suggestion (AKA, antenna keep-out area) 9
2.4. Footprint & design guide 10
2.5. Pin assignment 11

3. Main chip solution 16

4. Shipment packaging information 17
4.1. Marking on metal shield 20
4.2. Packaging Info 21
4.2.1. Tray packaging 21
4.2.2. Reel packaging 23
4.3. Order code 24

5. Specification 26
5.1. Recommended operating conditions 26
5.2. Radio specifications 26
5.2.1. General radio characteristics 26
5.2.2. Radio current consumption (Transmitter) 27
5.2.3. Radio current consumption (Receiver) 27
5.2.4. Transmitter specification 27
5.2.5. Receiver operation 28
5.2.6. RX selectivity 28
5.2.7. RX intermodulation 30
5.2.8. Radio timing parameters 31
5.2.9. RSSI specifications 31
5.3. GPIO electrical specification 32
5.4. Absolute maximum ratings 33

6. Block Diagram 34

7. Antenna 35

8. Reference circuit 36

9. Certification 37
9.1. Declaration ID for Bluetooth 37
9.2. FCC Certificate (USA) 38
9.3. TELEC Certificate (Japan) 41
9.4. NCC Certificate (Taiwan) 42
9.5. CE (EU) & RCM (Australia & New Zealand) test report 43
9.6. IC Certificate (Canada) 51
9.7. SRRC Certificate (China) 52
9.8. KC Certificate (South Korea) 53
9.9. WPC Certificate (India) 54
9.10. EU and UKCA Declarations of Conformity 56
9.11. RoHS & REACH report 56
9.12. End-product label 56
9.12.1. FCC (USA) 57
9.12.2. TELEC (Japan) 57
9.12.3. NCC (Taiwan) 57
9.12.4. IC (Canada) 58
9.13. Compliance and Certification 59
9.13.1. List of Applicable FCC Rules 59
9.13.2. RF Exposure Considerations 59
9.13.3. Antennas 60
9.13.4. Information on Test Modes and Additional Testing Requirements 61
9.13.5. Additional Testing, Part 15 Subpart B Disclaimer 61
9.13.6. Note EMI Considerations 61
9.13.7. How to Make Changes 62

10. Notes and Cautions 63

11. Useful links 64

Full list of Raytac's Wi-Fi modules 65

Full list of Raytac's Bluetooth modules 66

Release Note 72

1. Overall introduction

Raytac's AN54LQ family is a Bluetooth® 6.0 stack (Bluetooth low energy or BLE) modules designed based on **Nordic nRF54L15, nRF54L10, and nRF54L05 SoC solution**, which incorporates: **GPIO**, **QSPI (emulated)**, **SPI**, **UART**, **I2C**, **I2S, PDM, PWM, ADC** and **NFC** interfaces for connecting peripherals and sensors.

Product Character:

1. MCU (Microcontroller Unit) featuring a 128 MHz Arm Cortex-M33 processor.
2. **AN54LQ-U15** Embedded **1524 KB** NVM and up to **256 KB** RAM.
   AN54LQ-U10 Embedded **1012 KB** NVM and up to **192 KB** RAM.
   AN54LQ-U05 Embedded **500 KB** NVM and up to **96 KB** RAM.
3. An integrated RISC-V coprocessor.
4. The multiprotocol 2.4 GHz radio modes are supported based on customer preference.
5. Compact size with **(L) 14 x (W) 9.5 x (H) 1.85mm**
6. Wide supply voltage range **1.7V to 3.6V.**
7. Operation temperature from **-40℃ to 85℃.**
8. Up to **31** GPIOs.

1.1. Application

- IoT
  - Smart home sensors and actuators
  - Industrial sensors and actuators
  - Gateways and hubs
- Advanced computer peripherals and I/O devices
  - Keyboard
  - Mouse
  - Stylus
- Interactive entertainment devices
  - Remote controls
  - Gaming controllers
- Safety and security
  - Access control
  - Asset tracking
- Wearable health and fitness monitoring
- Lighting control

1.2. Features

- Multi-protocol 2.4GHz radio
- 128MHz Arm Cortex-M33 with Thumb-2 (16/32-bit instruction set)
- 1524KB flash programmed memory and 256KB RAM
- 128-bit AES / ECB / CCM / AAR co-processor
- Up to +7dBm configurable output power
- RSSI (1dB resolution)


Peripherals

- 128 MHz RISC-V coprocessor which is a fast, lightweight peripheral processor (FLPR)
- Timer counter
  - 7 x 32-bit
  - 2 x 24-bit RTC
- Fully featured serial interface with EasyDMA support including:
  - One high-speed SPIM up to 32 MHz, four up to 8 MHz
  - One high-speed UARTE up to 4 Mbps, four up to 1 Mbps
  - I2C up to 400 kHz
- Three pulse width modulator (PWM) units with EasyDMA
- I2S two channel Inter-IC sound interface
- ADC with up to eight programmable gain channels.
- Pulse density modulation (PDM) interface
- Near field communication (NFC)
- Quadrature decoders(QDEC)
- Temperature sensor

2. Product dimension

2.1. PCB dimensions & Pin indication


- **AN54LQ-U15 / AN54LQ-U10 / AN54LQ-U05**





PCB Size (in mm)			
	Min	Norm	Max
L	-0.15	14.0	+0.20
W		9.5	
H		1.85	

2.2. Recommended layout of solder pad

Graphs are all in Top View, Unit in mm.







Top View (Unit: mm)
9.5
14
0.5
0.5
0.4
×41_0.5×0.4mm
8.1
9
9.65
8.85
9.95
9.25
8.55
7.85
7.15
6.45
5.75
5.05
4.35
3.65
2.95
2.25
1.55
0.5
0
0
0.55
1.25
1.95
2.65
3.35
4.05
4.75
5.45
6.15
6.85
7.55
8.25
8.95
9.5
14

2.3. RF layout suggestion (AKA, antenna keep-out area)

Please ensure that no ground pad overlaps the “No Ground-Pad Area”, as shown in the images below. This is important to maintain antenna performance and to prevent potential short circuits within the module.


You are welcome to send us your design files for review at sales@raytac.com or to your Raytac contact with email subject titled: “Layout Review – Raytac Model No. – Your company name”.




Top View

No Ground-Pad Area

Please add via holes in GROUND area as many as possible, especially around the four corners.



Top View



Perpective View

2.4. Footprint & design guide

Please visit "Support" page of our website to download. The package includes footprint, 2D/3D drawing, and reflow graph/solder profile.

2.5. Pin assignment

Pin No.	Name	Pin function	Description
(1)	**GND**	Ground	The pad must be connected to a solid ground plane
(2)	**P1.09**	Digital I/O	General-purpose I/O
	ASO [2]	Digital I/O	TAMPC active shield 2 output
	RADIO [0]	Digital I/O	RADIO DFEGPIO
(3)	**P1.10**	Digital I/O	General-purpose I/O
	ASI [2]	Digital I/O	TAMPC active shield 2 input
	RADIO [1]	Digital I/O	RADIO DFEGPIO
(4)	**P1.11**	Digital I/O	General-purpose I/O
			Clock pin
	ASO [3]	Digital I/O	TAMPC active shield 3 output
	RADIO [2]	Digital I/O	RADIO DFEGPIO
	AIN4	Analog input	Analog input
(5)	**P1.12**	Digital I/O	General-purpose I/O
			Clock pin
	ASI [3]	Digital I/O	TAMPC active shield 3 input
	RADIO [3]	Digital I/O	RADIO DFEGPIO
	AIN5	Analog input	Analog input
(6)	**P1.13**	Digital I/O	General-purpose I/O
	RADIO [4]	Digital I/O	RADIO DFEGPIO
	AIN6	Analog input	Analog input
(7)	**P1.14**	Digital I/O	General-purpose I/O
	RADIO [5]	Digital I/O	RADIO DFEGPIO
	AIN7	Analog input	Analog input
(8)	**DECD**	Power	0.9 V regulator supply decoupling
(9)	**DCC**	Power	DC/DC regulator output
(10)	**GND**	Ground	The pad must be connected to a solid ground plane
(11)	**VDD_NRF**	Power	Power-supply pin
(12)	**P1.00**	Digital I/O	General-purpose I/O
	XL1	Analog input	Connection for 32.768kHz crystal
(13)	**P1.01**	Digital I/O	General-purpose I/O
	XL2	Analog input	Connection for 32.768kHz crystal

Pin No.	Name	Pin function	Description
(14)	**GND**	Ground	The pad must be connected to a solid ground plane
(15)	**P1.02**	Digital I/O	General-purpose I/O
	NFC1	NFC input	NFC antenna connection
(16)	**P1.03**	Digital I/O	General-purpose I/O Clock pin
	NFC2	NFC input	NFC antenna connection
(17)	**P1.04**	Digital I/O	General-purpose I/O Clock pin
	ASO [0]	Digital I/O	TAMPC active shield 0 output
	AIN0	Analog input	Analog input
(18)	**P1.05**	Digital I/O	General-purpose I/O
	ASI [0]	Digital I/O	TAMPC active shield 0 input
	RADIO [6]	Digital I/O	RADIO DFEGPIO
	AIN1	Analog input	Analog input
(19)	**P1.06**	Digital I/O	General-purpose I/O
	ASO [1]	Digital I/O	TAMPC active shield 1 output
	AIN2	Analog input	Analog input
(20)	**P1.07**	Digital I/O	General-purpose I/O
	ASI [1]	Digital I/O	TAMPC active shield 1 input
	AIN3	Analog input	Analog input
(21)	**P1.08**	Digital I/O	General-purpose I/O GRTC CLKOUTFAST Clock pin
	EXTREF	Analog input	External reference for SAADC
(22)	**P2.00**	Digital I/O	General-purpose I/O SPIM DCX UARTE RXD FLPR.4 QSPI D3

Pin No.	Name	Pin function	Description
(23)	**P2.01**	Digital I/O	General-purpose I/O
			SPIM SCK
			SPIS SCK
			FLPR.0
			QSPI SCK
			Clock pin
(24)	**P2.02**	Digital I/O	General-purpose I/O
			SPIM SDO
			SPIS SDO
			UARTE TXD
			FLPR.1
			QSPI D0
			Serial wire output (SWO)
(25)	**P2.03**	Digital I/O	General-purpose I/O
			FLPR.3
			QSPI D2
(26)	**GND**	Ground	The pad must be connected to a solid ground plane
(27)	**P2.04**	Digital I/O	General-purpose I/O
			SPIM SDI
			SPIS SDI
			UARTE CTS
			FLPR.2
			QSPI D1
(28)	**P2.05**	Digital I/O	General-purpose I/O
			SPIM CS
			SPIS CS
			UARTE RTS
			FLPR.5
			QSPI CS

Pin No.	Name	Pin function	Description
(29)	**P2.06**	Digital I/O	General-purpose I/O
			FLPR.6
			SPIM SCK
			SPIS SCK
			Clock pin
	TRACECLK	Digital I/O	Trace clock
(30)	**P2.07**	Digital I/O	General-purpose I/O
			FLPR.7
			SPIM DCX
			UARTE RXD
	TRACEDATA [0]		Trace data
	SWO		Serial wire output (SWO)
(31)	**P2.08**	Digital I/O	General-purpose I/O
			FLPR.8
			SPIM SDO
			SPIS SDO
			UARTE TXD
	TRACEDATA [1]	Digital I/O	Trace data
(32)	**P2.09**	Digital I/O	General-purpose I/O
			FLPR.9
			SPIM SDI
			SPIS SDI
			UARTE CTS
	TRACEDATA [2]	Digital I/O	Trace data
(33)	**P2.10**	Digital I/O	General-purpose I/O
			FLPR.10
			SPIM CS
			SPIS CS
			UARTE RTS
	TRACEDATA [3]	Digital I/O	Trace data
(34)	**P0.00**	Digital I/O	General-purpose digital I/O
(35)	**P0.01**	Digital I/O	General-purpose digital I/O

Pin No.	Name	Pin function	Description
(36)	SWDIO	Debug	Serial wire data. Bidirectional with standard-drive and on-chip pull-down.
(37)	SWDCLK	Debug	Serial wire clock. Input with on-chip pull-up.
(38)	P0.03	Digital I/O	General-purpose I/O GRTC PWM Clock pin
(39)	RESET	Reset	Pin reset with on-chip pull-up (low active)
(40)	P0.04	Digital I/O	General-purpose I/O GRTC CLKOUT32K Clock pin
(41)	P0.02	Digital I/O	General-purpose digital I/O

3. Main chip solution

RF IC	Crystal Frequency
Nordic NRF54L15 / QFN	
Nordic NRF54L10 / QFN	**32MHz**
Nordic NRF54L05 / QFN	

The 32MHz crystal is already integrated inside the module.
The crystal load capacitance has already been optimized in the module design.

4. Shipment packaging information

AN54LQ-15 Series

Model	Antenna	Photo
AN54LQ-15	Chip/Ceramic	
AN54LQ-P15	PCB/Printed	
AN54LQ-U15	U.FL/Connector	

- Unit weight of module:

AN54LQ-15 : 0.51 g (±0.02 g) ; AN54LQ-P15 : 0.51 g (±0.02 g) ; AN54LQ-U15 : 0.55 g (±0.02 g) ;

- Packaging type: Tray or Tape & Reel.

	Tray (PET / APET)	**Tape & Reel**
MPQ (Min. Package Q'ty)	88 pcs per tray	1,500 pcs per reel
Carton Contents (per carton)	1,760 pcs	1,500 pcs
Carton Dimension (L) x (W) x (H) cm	37 x 21 x 13	37 x 36 x 6
Gross Weight	about 2.6 kgs	about 2.1 kgs

AN54LQ-10 Series

Model	Antenna	Photo
AN54LQ-10	Chip/Ceramic	
AN54LQ-P10	PCB/Printed	
AN54LQ-U10	U.FL/Connector	

- Unit weight of module:

AN54LQ-10 : 0.51 g (±0.02 g) ; AN54LQ-P10 : 0.51 g (±0.02 g) ; AN54LQ-U10 : 0.55 g (±0.02 g) ;

- Packaging type: Tray or Tape & Reel.

	Tray (PET / APET)	**Tape & Reel**
MPQ (Min. Package Q'ty)	88 pcs per tray	1,500 pcs per reel
Carton Contents (per carton)	1,760 pcs	1,500 pcs
Carton Dimension (L) x (W) x (H) cm	37 x 21 x 13	37 x 36 x 6
Gross Weight	about 2.6 kgs	about 2.1 kgs

AN54LQ-05 Series

Model	Antenna	Photo
AN54LQ-05	Chip/Ceramic	
AN54LQ-P05	PCB/Printed	
AN54LQ-U05	U.FL/Connector	

- Unit weight of module:


AN54LQ-05 : 0.51 g (±0.02 g) ; AN54LQ-P05 : 0.51 g (±0.02 g) ; AN54LQ-U05 : 0.55 g (±0.02 g) ;

- Packaging type: Tray or Tape & Reel.

	Tray (PET / APET)	**Tape & Reel**
MPQ (Min. Package Q'ty)	88 pcs per tray	1,500 pcs per reel
Carton Contents (per carton)	1,760 pcs	1,500 pcs
Carton Dimension (L) x (W) x (H) cm	37 x 21 x 13	37 x 36 x 6
Gross Weight	about 2.6 kgs	about 2.1 kgs

4.1. Marking on metal shield

Label context on metal shield is as below:



4.2. Packaging Info

4.2.1. Tray packaging

Anti-static trays are specifically designed for mass production and are fully compatible with standard SMT automated assembly lines. To optimize manufacturing efficiency, standard PET or APET anti-static materials are utilized, both ensuring excellent mechanical stability and ESD protection.

Both tray variants share identical physical dimensions and structural designs, differing only in the text marking printed on the surface for material identification.




Figure 1: Tray specification with PET marking





Figure 2: Tray specification with APET marking

4.2.2. Reel packaging



W	24.00	±0.30
P1	16.00	±0.10
E1	1.75	±0.10
F	11.50 ±0.10	
D0	1.50	+0.1/-0
P0	4.00	±0.10
P2	2.00 ±0.10	
A0	9.60	±0.10
B0	14.70	±0.10
K0	2.30	±0.10
T	0.30	±0.05

4.3. Order code

Each model has two options of packaging. Please use following part no. when placing order to us.

AN54LQ-15 Series

Model	Tray	Tape & Reel
AN54LQ-15	(PET) MD-240A8-001 (APET) MD-240A8-001A	MD-240A8-001R
AN54LQ-P15	(PET) MD-240A8-002 (APET) MD-240A8-002A	MD-240A8-002R
AN54LQ-U15	(PET) MD-240A8-003 (APET) MD-240A8-003A	MD-240A8-003R

MPQ of Reel packaging is 1,500 pcs and Tray packaging is 88 pcs.

AN54LQ-10 Series

Model	Tray	Tape & Reel
AN54LQ-10	(PET) MD-240A8-011 (APET) MD-240A8-011A	MD-240A8-011R
AN54LQ-P10	(PET) MD-240A8-012 (APET) MD-240A8-012A	MD-240A8-012R
AN54LQ-U10	(PET) MD-240A8-013 (APET) MD-240A8-013A	MD-240A8-013R

MPQ of Reel packaging is 1,500 pcs and Tray packaging is 88 pcs.

AN54LQ-05 Series

Model	Tray	Tape & Reel
AN54LQ-05	(PET) MD-240A8-014 (APET) MD-240A8-014A	MD-240A8-014R
AN54LQ-P05	(PET) MD-240A8-015 (APET) MD-240A8-015A	MD-240A8-015R
AN54LQ-U05	(PET) MD-240A8-016 (APET) MD-240A8-016A	MD-240A8-016R

MPQ of Reel packaging is 1,500 pcs and Tray packaging is 88 pcs.

5. Specification

Any technical spec shall refer to Nordic's official documents as final reference. Contents below are from "nRF54L15_nRF54L10_nRF54L05 Product Specification v1.0", please click to download full spec.

5.1. Recommended operating conditions

Symbol	Parameter	Min.	Nom.	Max.	Units
VDD	VDD supply voltage	1.7		3.6	V
VDD_{EXT}	VDD supply voltage under extended operating temperature	1.7		3.4	V
VDD_{POR}	VDD supply voltage needed during power-on reset	1.75			V
TA	Operating temperature	-40	25	85	°C
TA_{EXT}	Extended operating temperature	85		105	°C
T_{RST}	Recommended storage temperature			40	°C
RH_{RST}	Recommended storage relative humidity			90	%

The operating conditions are the physical parameters that the device can operate within.

5.2. Radio specifications

5.2.1. General radio characteristics

Symbol	Parameter	Min.	Typ.	Max.	Units
f_{op}	Operating frequencies	2400		2500	MHz
$f_{PLL,CH,SP}$	Channel spacing		1		MHz
$f_{DELTA,1M}$	Frequency deviation @ 1 Mbps		± 160		kHz
$f_{DELTA,BLE,1M}$	Frequency deviation @ Bluetooth LE 1 Mbps		±250		kHz
$f_{DELTA,2M}$	Frequency deviation @ 2 Mbps		±320		kHz
$f_{DELTA,BLE,2M}$	Frequency deviation @ Bluetooth LE 2 Mbps		±500		kHz
$f_{DELTA,4M}$	Frequency deviation @ 4 Mbps		±1000		kHz
fsk_{BPS}	On-the-air data rate	125		4000	kbps
$f_{chip,\ IEEE\ 802.15.4}$	Chip rate in IEEE 802.15.4 mode		2000		kchip/s

5.2.2. Radio current consumption (Transmitter)

Symbol	Description	Min.	Typ.	Max.	Units
$I_{TX,MaxdBm,QFN}$	TX only run current for QFN package, P_{RF} at maximum power setting		9.1		mA
$I_{TX,MaxdBm,CSP}$	TX only run current for CSP package, P_{RF} at maximum power setting		9.7		mA
$I_{TX,0dBM}$	TX only run current, P_{RF} = 0 dBm		3.7		mA
$I_{TX,MINUS4dBM}$	TX only run current, P_{RF} = -4 dBm		2.8		mA
$I_{TX,MINUS8dBM}$	TX only run current, P_{RF} = -8 dBm		2.2		mA
$I_{TX,MINUS12dBM}$	TX only run current P_{RF} = -12 dBm		1.9		mA
$I_{TX,MINUS16dBM}$	TX only run current P_{RF} = -16 dBm		1.7		mA
$I_{TX,MINUS40dBM}$	TX only run current P_{RF} = -40 dBm		1.2		mA

5.2.3. Radio current consumption (Receiver)

Symbol	Description	Min.	Typ.	Max.	Units
$I_{RX,1M}$	RX only run current, 1 Mbps/1 Mbps Bluetooth LE mode		2.1		mA
$I_{RX,2M}$	RX only run current, 2 Mbps/2 Mbps Bluetooth LE mode		2.1		mA
$I_{START,RX,1M}$	RX start-up current, 1 Mbps/1 Mbps Bluetooth LE mode		1.6		mA

5.2.4. Transmitter specification

Symbol	Description	Min.	Typ.	Max.	Units
$P_{RF,QFN}$	Maximum output power for QFN package		7		dBm
$P_{RF,CSP}$	Maximum output power for CSP package		8		dBm
P_{RFCR}	RF power accuracy	-2		2	dB
$P_{RF1,BLE1M,2MHz}$	Adjacent Channel Transmit Power 2 MHz (1 Mbps Bluetooth LE mode)		-48		dBc
$P_{RF1,BLE1M,3MHz}$	Adjacent Channel Transmit Power 3 MHz (1 Mbps Bluetooth LE mode)		-54		dBc
$P_{RF1,BLE2M,4MHz}$	Adjacent Channel Transmit Power 4 MHz (2 Mbps Bluetooth LE mode)		-51		dBc
$P_{RF1,BLE2M,6MHz}$	Adjacent Channel Transmit Power 6 MHz (2 Mbps Bluetooth LE mode)		-56		dBc
E_{vm}	Error vector magnitude in IEEE 802.15.4 mode		2		%rms
$P_{harm2nd,\ IEEE\ 802.15.4}$	2nd harmonics in IEEE 802.15.4 mode		-63		dBm
$P_{harm3rd,\ IEEE\ 802.15.4}$	3rd harmonics in IEEE 802.15.4 mode		68		dBm

5.2.5. Receiver operation

Symbol	Description	Min.	Typ.	Max.	Units
$P_{RX,MAX}$	Maximum received signal strength at < 0.1% PER		0		dBm
$P_{SENS,IT,1M}$	Sensitivity, 1 Mbps nRF mode ideal transmitter [4]		-93		dBm
$P_{SENS,IT,2M}$	Sensitivity, 2 Mbps nRF mode ideal transmitter [4]		-90		dBm
$P_{SENS,IT,4M}$	Sensitivity, 4 Mbps nRF mode ideal transmitter [4]		-90		dBm
$P_{SENS,IT,SP,1M,BLE}$	Sensitivity, 1 Mbps Bluetooth LE ideal transmitter, packet length ≤ 37 bytes BER = 1E-3[5]		-96[6]		dBm
$P_{SENS,IT,LP,IM,BLE}$	Sensitivity, 1 Mbps Bluetooth LE ideal transmitter, packet length ≥ 128 bytes BER = 1E-4		-95		dBm
$P_{SENS,IT,SP,2M,BLE}$	Sensitivity, 2 Mbps Bluetooth LE ideal transmitter, packet length ≤ 37 bytes		-94		dBm
$P_{SENS,IT,BLE\ LE125k}$	Sensitivity, 125 kbps Bluetooth LE mode		-104		dBm
$P_{SENS,IT,BLE\ LE500k}$	Sensitivity, 500 kbps Bluetooth LE mode		-99		dBm
$P_{SENS,IEEE\ 802.15.4}$	Sensitivity in IEEE 802.15.4 mode		-102		dBm

[4] *Typical sensitivity applies when RXADDRESS.ADDRO is used for receiver address. When RXADDRESS.ADDR[1 ... 7] are used for receiver address, the typical sensitivity for this mode is degraded by 3 dB.*

[5] *As defined in the Bluetooth Core Specification v4.0 Volume 6: Core System Package (Low Energy Controller Volume).*

[6] *QFN package sensitivity is degraded by approximately 1 dB compared to the provided value.*

5.2.6. RX selectivity

Symbol	Description	Min.	Typ.	Max.	Units
$C/I_{1M,co\text{-}channel}$	1 Mbps mode, co-channel interference		9		dB
$C/I_{1M,-1MHz}$	1 Mbps mode, Adjacent (-1 MHz) interference		-4		dB
$C/I_{1M,+1MHz}$	1 Mbps mode, Adjacent (+1 MHz) interference		-9		dB
$C/I_{1M,-2MHz}$	1 Mbps mode, Adjacent (-2 MHz) interference		-28		dB
$C/I_{1M,+2MHz}$	1 Mbps mode, Adjacent (+2 MHz) interference		-40		dB
$C/I_{1M,-3MHz}$	1 Mbps mode, Adjacent (-3 MHz) interference		-39		dB
$C/I_{1M,+3MHz}$	1 Mbps mode, Adjacent (+3 MHz) interference		-43		dB
$C/I_{1M,\pm6MHz}$	1 Mbps mode, Adjacent (≥6 MHz) interference		-48		dB
$C/I_{1MBLE,co\text{-}channel}$	1 Mbps Bluetooth LE mode, co-channel interference		6		dB
$C/I_{1MBLE,-1MHz}$	1 Mbps Bluetooth LE mode, Adjacent (-1 MHz) interference		-2		dB
$C/I_{1MBLE,+1MHz}$	1 Mbps Bluetooth LE mode, Adjacent (+1 MHz) interference		-6		dB
$C/I_{1MBLE,-2MHz}$	1 Mbps Bluetooth LE mode, Adjacent (-2 MHz) interference		-29		dB
$C/I_{1MBLE,+2MHz}$	1 Mbps Bluetooth LE mode, Adjacent (+2 MHz) interference		-43		dB
$C/I_{1MBLE,>3MHz}$	1 Mbps Bluetooth LE mode, Adjacent (≥3 MHz) interference		-46		dB

Symbol	Description	Min.	Typ.	Max.	Units
$C/I_{1MBLE,image}$	Image frequency interference		-29		dB
$C/I_{1MBLE,image,1MHz}$	Adjacent (1 MHz) interference to in-band image frequency		-39		dB
$C/I_{2M,co-channel}$	2 Mbps mode, co-channel interference		10		dB
$C/I_{2M,-2MHz}$	2 Mbps mode, Adjacent (-2 MHz) interference		-5		dB
$C/I_{2M,+2MHz}$	2 Mbps mode, Adjacent (+2 MHz) interference		-9		dB
$C/I_{2M,-4MHz}$	2 Mbps mode, Adjacent (-4 MHz) interference		-27		dB
$C/I_{2M,+4MHz}$	2 Mbps mode, Adjacent (+4 MHz) interference		-42		dB
$C/I_{2M,-6MHz}$	2 Mbps mode, Adjacent (-6 MHz) interference		-38		dB
$C/I_{2M,+6MHz}$	2 Mbps mode, Adjacent (+6 MHz) interference		-45		dB
$C/I_{2M,\geq12MHz}$	2 Mbps mode, Adjacent (≥12 MHz) interference		-50		dB
$C/I_{2MBLE,co-channel}$	2 Mbps Bluetooth LE mode, co-channel interference		6		dB
$C/I_{2MBLE,-2MHz}$	2 Mbps Bluetooth LE mode, Adjacent (-2 MHz) interference		-2		dB
$C/I_{2MBLE,+2MHz}$	2 Mbps Bluetooth LE mode, Adjacent (+2 MHz) interference		-6		dB
$C/I_{2MBLE,-4MHz}$	2 Mbps Bluetooth LE mode, Adjacent (-4 MHz) interference		-29		dB
$C/I_{2MBLE,+4MHz}$	2 Mbps Bluetooth LE mode, Adjacent (+4 MHz) interference		-44		dB
$C/I_{2MBLE,\geq6MHz}$	2 Mbps Bluetooth LE mode, Adjacent (≥6 MHz) interference		-46		dB
$C/I_{4M,co-channel}$	4 Mbps mode, co-channel interference		6		dB
$C/I_{4M,-4MHz}$	4 Mbps mode, Adjacent (-4 MHz) interference		-4		dB
$C/I_{4M,+4MHz}$	4 Mbps mode, Adjacent (+4 MHz) interference		-11		dB
$C/I_{4M,-8MHz}$	4 Mbps mode, Adjacent (-8 MHz) interference		-27		dB
$C/I_{4M,+8MHz}$	4 Mbps mode, Adjacent (+8 MHz) interference		-46		dB
$C/I_{4M,-12MHz}$	4 Mbps mode, Adjacent (-12 MHz) interference		-40		dB
$C/I_{4M,+12MHz}$	4 Mbps mode, Adjacent (+12 MHz) interference		-50		dB
$C/I_{4M,\geq24MHz}$	4 Mbps mode, Adjacent (≥24 MHz) interference		-56		dB
$C/I_{2MBLE,image}$	Image frequency interference		-29		dB
$C/I_{2MBLE,image,2MHz}$	Adjacent (2 MHz) interference to in-band image frequency		-38		dB

RX selectivity with equal modulation on interfering signal [7]

[7] *Desired signal level at P_{IN} = -67 dBm. One interferer is used, having equal modulation as the desired signal.The input power of the interferer where the sensitivity equals BER = 0.1% is presented.*

Symbol	Description	Min.	Typ.	Max.	Units
$C/I_{125k\ BLE\ LR,co\text{-}channel}$	125 kbps Bluetooth LE LR mode, co-channel interference		1		dB
$C/I_{125k\ BLE\ LR,-1MHz}$	125 kbps Bluetooth LE LR mode, Adjacent (-1 MHz) interference		-13		dB
$C/I_{125k\ BLE\ LR,+1MHz}$	125 kbps Bluetooth LE LR mode, Adjacent (+1 MHz) interference		-16		dB
$C/I_{125k\ BLE\ LR,-2MHz}$	125 kbps Bluetooth LE LR mode, Adjacent (-2 MHz) interference		-36		dB
$C/I_{125k\ BLE\ LR,+2MHz}$	125 kbps Bluetooth LE LR mode, Adjacent (+2 MHz) interference		-52		dB
$C/I_{125k\ BLE\ LR,\geq 3MHz}$	125 kbps Bluetooth LE LR mode, Adjacent (≥3 MHz) interference		-55		dB
$C/I_{125k\ BLE\ LR,image}$	Image frequency interference		-36		dB
$C/I_{IEEE\ 802.15.4,-5MHz}$	IEEE 802.15.4 mode, Adjacent (-5 MHz) rejection		-35		dB
$C/I_{IEEE\ 802.15.4,+5MHz}$	IEEE 802.15.4 mode, Adjacent (+5 MHz) rejection		-38		dB
$C/I_{IEEE\ 802.15.4,\pm 10MHz}$	IEEE 802.15.4 mode, Alternate (±10 MHz) rejection		-50		dB

5.2.7. RX intermodulation

Symbol	Description	Min.	Typ.	Max.	Units
$P_{IMD,5TH,1M,BLE}$	IMD performance, Bluetooth LE 1 Mbps, 5th offset channel, packet length ≤37 bytes		-19		dBm
$P_{IMD,5TH,2M,BLE}$	IMD performance, Bluetooth LE 2 Mbps, 5th offset channel, packet length ≤37 bytes		-16		dBm

RX intermodulation: Desired signal level at P_IN = -64 dBm. Two interferers with equal input power are used.
The interferer closest in frequency is not modulated, the other interferer is modulated equal with the desired signal.
The input power of the interferers where the sensitivity equals BER = 1E-3 is presented.

5.2.8. Radio timing parameters

Symbol	Description	Min.	Typ.	Max.	Units
$t_{TXEN,BLE,1M}$	Time between TXEN task and READY event after channel FREQUENCY configured (1 Mbps Bluetooth LE and 150 µs TIFS)		140		µs
$t_{TXEN,FAST,BLE,1M}$	Time between TXEN task and READY event after channel FREQUENCY configured (1 Mbps Bluetooth LE with fast ramp-up and 150 µs TIFS)		40		µs
$t_{TXDIS,BLE,1M}$	When in TX, delay between DISABLE task and DISABLED event for MODE = Nrf_1Mbit and MODE = Ble_1Mbit		2		µs
$t_{RXEN,BLE,1M}$	Time between the RXEN task and READY event after channel FREQUENCY configured (1 Mbps Bluetooth LE)		134		µs
$t_{RXEN,FAST,BLE,1M}$	Time between the RXEN task and READY event after channel FREQUENCY configured (1 Mbps Bluetooth LE with fast ramp-up)		40		µs
$t_{RXDIS,BLE,1M}$	When in RX, delay between DISABLE task and DISABLED event for MODE = Nrf_1Mbit and MODE = Ble_1Mbit		1		µs
$t_{TXDIS,BLE,2M}$	When in TX, delay between DISABLE task and DISABLED event for MODE = Nrf_2Mbit and MODE = Ble_2Mbit		2		µs
$t_{RXDIS,BLE,2M}$	When in RX, delay between DISABLE task and DISABLED event for MODE = Nrf_2Mbit and MODE = Ble_2Mbit		1		µs
$t_{TXEN,IEEE802.15.4}$	Time between TXEN task and READY event after channel FREQUENCY configured (IEEE 802.15.4 mode)		130		µs
$t_{TXEN,FAST,IEEE802.15.4}$	Time between TXEN task and READY event after channel FREQUENCY configured (IEEE 802.15.4 mode with fast ramp-up)		40		µs
$t_{TXDIS,IEEE802.15.4}$	When in TX, delay between DISABLE task and DISABLED event (IEEE 802.15.4 mode)		18		µs
$t_{RXEN,IEEE802.15.4}$	Time between the RXEN task and READY event after channel FREQUENCY configured (IEEE 802.15.4 mode)		130		µs
$t_{RXEN,FAST,IEEE802.15.4}$	Time between the RXEN task and READY event after channel FREQUENCY configured (IEEE 802.15.4 mode with fast ramp-up)		40		µs
$t_{RXDIS,IEEE802.15.4}$	When in RX, delay between DISABLE task and DISABLED event (IEEE 802.15.4 mode)		0.2		µs
$t_{RX\text{-}to\text{-}TX\ turnaround,\ IEEE802.15.4}$	Maximum RX-to-TX turnaround time in IEEE 802.15.4 mode		17		µs

5.2.9. RSSI specifications

Symbol	Description	Min.	Typ.	Max.	Units
$RSSI_{ACC}$	RSSI accuracy in the range −90 to −30 dBm		±2		dB
$RSSI_{RESOLUTION}$	RSSI resolution		1		dB
$RSSI_{PERIOD}$	RSSI sampling time from RSSISTART task		0.25		µs
$RSSI_{SETTLE}$	RSSI settling time after signal level change		15	20	µs

5.3. GPIO electrical specification


Symbol	Description	Min.	Typ.	Max.	Units
V_{IH}	Input high voltage	0.7 × VDD		VDD	V
V_{IL}	Input low voltage	VSS		0.3 × VDD	V
$V_{OH,SD}$	Output high voltage, standard drive, 0.5 mA, VDD ≥ 1.7 V	VDD − 0.4		VDD	V
$V_{OH,HDH}$	Output high voltage, high drive, 5 mA, VDD ≥ 2.7 V	VDD − 0.4		VDD	V
$V_{OH,HDL}$	Output high voltage, high drive, 3 mA, VDD ≥ 1.7 V	VDD − 0.4		VDD	V
$V_{OL,SD}$	Output low voltage, standard drive, 0.5 mA, VDD ≥ 1.7 V	VSS		VSS + 0.4	V
$I_{OL,SD}$	Current at VSS + 0.4 V, output set low, standard drive, VDD ≥ 1.7 V	1	3	4	mA
$I_{OL,HDL}$	Current at VSS + 0.4 V, output set low, high drive, VDD ≥ 1.7 V	3			mA
$I_{OL,ED}$	Current at VSS + 0.4 V, output set low, extra drive, VDD ≥ 1.7 V	16			mA
$I_{OH,SD}$	Current at VDD − 0.4 V, output set high, standard drive, VDD ≥ 1.7 V	1	3	4	mA
$I_{OH,HDL}$	Current at VDD − 0.4 V, output set high, high drive, VDD ≥ 1.7 V	4			mA
$I_{OH,ED}$	Current at VDD − 0.4 V, output set high, extra drive, VDD ≥ 1.7 V	14			mA
$I_{GPIO,TOTAL}$	Recommended maximum sustained current drawn by all GPIOs			15	mA
$t_{HR,12pF}$	Rise/Fall time, high drive mode, 20–80%, 12 pF load[1]		4		ns
$t_{ER,12pF}$	Rise/Fall time, extra drive mode, 20–80%, 12 pF load[1]		0.9		ns
R_{PU}	Pull-up resistance	12	14	16	kΩ
R_{PD}	Pull-down resistance	12	14	18	kΩ
$t_{OE,ED}$	Output enable delay in extra drive mode			855	ns
C_{PAD}	Pad capacitance		1		pF
C_{PAD_NFC}	Pad capacitance on NFC pads		5		pF

5.4. Absolute maximum ratings

	Parameter	Min.	Max.	Unit
Supply voltage				
VDD	VDD supply voltage	-0.3	3.9	V
VDD_{EXT}	VDD supply voltage under extended operating temperature	-0.3	3.7	V
I/O pin voltage				
$V_{I/O}$, VDD ≤ 3.6 V	IO voltage	-0.3	VDD + 0.3	V
$V_{I/O}$, VDD > 3.6 V	IO voltage	-0.3	3.9	V
$V_{I/O,EXT}$,VDD_{EXT} ≤ 3.4 V	IO voltage under extended operating temperature	-0.3	VDD + 0.3	V
$V_{I/O,EXT}$,VDD_{EXT} > 3.4 V	IO voltage under extended operating temperature	-0.3	3.7	V
Radio				
RF input level			10	dBm
RRAM memory				
Endurance		10,000		Write / rewrite cycles
Retention at 85 °C		10		y
Retention at 105 °C		2		y

	Note	Min.	Max.	Units
Environmental – QFN package types				
Storage temperature		-40	+125	°C
Reflow soldering temperature	Reflow cycle time is 30 seconds with 3 maximum reflow cycles		260	°C
Moisture Sensitivity Level (MSL)			2	
ESD Human Body Model (HBM)			1	KV
ESD Charged Device Model (CDM)			500	V
Environmental – CSP package types				
Storage temperature	Recommended storage condition is < 40 °C and < 90% RH (relative humidity)	-40	+125	°C
Reflow soldering temperature	Reflow cycle time is 30 seconds with 3 maximum reflow cycles.		260	°C
Moisture Sensitivity Level (MSL)			1	
ESD Human Body Model (HBM)			3	KV
ESD Charged Device Model (CDM)			250	V

6. Block Diagram



7. Antenna

Below chart shows a few options of external antenna which has been tested and approved to use with AN54LQ-U15. Please check *9 Certification* for more details.

#	Photo	Model No.	Type	Supplier	Gain	Spec	Certification
1		ANTX100 ETHAB24553	External	Yageo	2.2 dBi		**FCC, IC, TELEC, KC NCC, SRRC, CE, RCM**
2		RFA-02-5 -F17H170100B	External	Aristotle	5 dBi		**FCC, IC, TELEC KC NCC, SRRC**
3		ANTX100 P011B24003	PCB	Yageo	2.2 dBi		**FCC, IC, TELEC, KC NCC, SRRC, CE, RCM**
4		ANTX100 P111B24003	PCB	Yageo	3.3 dBi		**FCC, IC, TELEC, KC, NCC, SRRC**

**** End-product may need to perform further testing when applying CE, RCM and SRRC. Others are modular approval.***

**** Our certificate(s) might not be applicable when using antenna apart from above list.***

8. Reference circuit

Module is pre-programmed with Raytac's testing code. Default is using "DC-DC mode". The Nordic NCS firmware is set to use external 32.768KHz so please add it to make module work.


REMARK:

***** DECD decoupling capacitor (2.2μF) is already inside the module. *****

***** When enabling the DC/DC regulator, the device checks if an inductor (L1) is connected to the DCC pin. If L1 is not detected, the device remains in LDO mode.*****

***** When NOT using NFC, please remove NFC1 / C19 / C20. *****

***** When using internal 32.768KHz RC oscillator, please remove X2 / C12 / C13. *****



9. Certification

9.1. Declaration ID for Bluetooth

BT 6.0

Declaration ID	QDID(s) and Included DN(s)	Company	Specification Name
Q373526	Q360916 – Controller Subsystem Q361608 – Host Subsystem	Raytac Corporation	6.0

Profile Description	Service Description
Alert Notification Profile	Alert Notification Service
Blood Pressure Profile	Blood Pressure Service
	Device Information Service
Cycling Speed & Cadence Profile	Cycling Speed & Cadence Service
	Device Information Service
Glucose Profile	Glucose Service
	Device Information Service
Health Thermometer Profile	Health Thermometer Service
	Device Information Service
Heart Rate Profile	Heart Rate Service
	Device Information Service
HID over GATT Profile	HID Service
	Battery Service
Proximity Profile	Link Loss Service
	Immediate Alert Service
	TX Power Service
Running Speed & Cadence Profile	Running Speed & Cadence Service
	Device Information Service
Time Profile	Time Profile Service
Glucose Profile (Central)	
Mesh Profile	Mesh Provisioning Service
	Mesh Proxy Service

9.2. FCC Certificate (USA)

2.4GHz wireless module

kiwa

PRODUCTS
RvA C 002

TCB

GRANT OF EQUIPMENT
AUTHORIZATION

Certification
Issued Under the Authority of the
Federal Communications Commission
By:

TCB

Kiwa Nederland B.V.
Wilmersdorf 50
Apeldoorn, NL-7300 AC
Netherlands

Date of Grant: 07/30/2025

Application
Dated: 07/23/2025

Raytac Corp.
8F, No.788-1, Zhongzheng Rd., Zhonghe Dist.,
New Taipei City,, 235
Taiwan

Attention: Lyon Liu , President

NOT TRANSFERABLE

EQUIPMENT AUTHORIZATION is hereby issued to the named GRANTEE, and is VALID ONLY for the equipment identified hereon for use under the Commission's Rules and Regulations listed below.

FCC IDENTIFIER:	SH6AN54LQ
Name of Grantee:	Raytac Corp.
Equipment Class:	**Digital Transmission System**
Notes:	**Bluetooth Low Energy Module**
Modular Type:	**Single Modular**

Grant Notes	FCC Rule Parts	Frequency Range (MHZ)	Output Watts	Frequency Tolerance	Emission Designator
	15C	**2402.0 - 2480.0**	**0.006**		

Power output listed is conducted. This grant is valid only when the module is sold to OEM integrators and must be installed by the OEM or OEM integrators. The antenna's as listed in this application must be installed to provide a separation distance of at least 20 cm from all persons and must not be co-located or operating in conjunction with any other antenna or transmitter. End-users may not be provided with the module installation instructions. OEM integrators and end-users must be provided with transmitter operating conditions for satisfying RF exposure compliance.

Certificate No.: 252181162/AA/00	Ron Scheepers Managing director	

RF EXPOSURE REPORT

Applicant:	Raytac Corp. 8F, No.788-1, Zhongzheng Rd., Zhonghe Dist., New Taipei City, 235, Taiwan
Manufacturer:	Raytac Corp. 8F, No.788-1, Zhongzheng Rd., Zhonghe Dist., New Taipei City, 235, Taiwan
Product Name:	Bluetooth Low Energy Module
Brand Name:	Raytac
Model No.:	AN54LQ
Family Model No.:	AN54LQ-P, AN54LQ-U
Model Difference:	Dimensions, Antenna type
FCC ID	SH6AN54LQ
IC:	8017A-AN54LQ
Date of EUT Received:	Feb. 05, 2025
Issue Date:	Jul. 21, 2025

Approved By John Yeh
John Yeh

We hereby certify that:

The above equipment was evaluated by SGS Taiwan Ltd. The evaluation in this report is in compliance with FCC Rule Part §2.1091, KDB 447498 D01 v06 and RSS-102 issue 6.

The results of this report relate only to the sample identified in this report.

VERIFICATION OF COMPLIANCE

Issue Date:	Jul. 11, 2025
Applicant:	Raytac Corp.
Address:	8F, No.788-1, Zhongzheng Rd., Zhonghe Dist., New Taipei City, 235, Taiwan
Manufacturer:	Raytac Corp.
Address:	8F, No.788-1, Zhongzheng Rd., Zhonghe Dist., New Taipei City, 235, Taiwan
Product:	Bluetooth Low Energy Module
Brand Name/Trade Mark:	Raytac
Model/Type:	AN54LQ
Added Model(s):	AN54LQ-P, AN54LQ-U
Applicable Standards:	47 CFR FCC Part 15 Subpart B ICES-003 Issue 7 : October 2020 ANSI C63.4 : 2014
Test Laboratory:	SGS Taiwan Ltd. Electromagnetic Compatibility Laboratory No.2, Keji 1st Rd., Guishan District, Taoyuan City, Taiwan
Test Report No.:	TMHY2502000327YE, dated on Jul. 11, 2025

Conclusion: Based upon a review of the Test Report(s), the tested sample of the product mentioned above is deemed to comply with the requirements of the above standards.

Note: This verification is only valid for the product and configuration described and in conjunction with the test report as detailed above.

Authorised Signatory:

Eddy Cheng

SGS Taiwan Ltd.
Eddy Cheng
Asst. Supervisor

9.3. TELEC Certificate (Japan)

1 Mbps & 2 Mbps

CERTIFICATE

kiwa

Certificate of
Radio Equipment in JAPAN
201-250520 / 00

Issued 25 July 2025

Page 1 of 5
This certificate has THREE Annexes

Kiwa Nederland B.V., operating as Japan Conformity Assessment Body (CAB ID Number: 201), according procedure RD_740, declares that the listed product complies with the Technical Regulations Conformity Certification of Specified Radio equipment (ordinance of MPT N° 37,1981)

Product description:	**Bluetooth Low Energy Module**
Trademark:	**Raytac**
Type designation:	**AN54LQ**
Hardware / Software:	**1 / 1**
Variants:	**See Annex 3**
Manufacturer:	**Raytac Corp.**
Address:	**8F., No. 788-1, Zhongzheng Rd., Zhonghe Dist.,**
City:	**235 New Taipei City**
Country:	**Taiwan**

This certificate is granted to:

Name:	**Raytac Corp.**
Address:	**8F., No. 788-1, Zhongzheng Rd., Zhonghe Dist.,**
City:	**235 New Taipei City**
Country:	**Taiwan**

Ron Scheepers
Managing director

Kiwa Nederland B.V.
Wilmersdorf 50
Postbus 137
7300 AC Apeldoorn
The Netherlands

https://www.kiwa.com/nl/en/markets/radio-wireless-and-electrical-equipment/

Chamber of commerce
08090048

PRODUCTS
RvA C 002

9.4. NCC Certificate (Taiwan)

1 Mbps & 2 Mbps

台灣檢驗科技股份有限公司

電信管制射頻器材型式認證證明

證照字號：型式字第 AM 號

一、申　請　者：勁達國際電子股份有限公司

二、地　　址：臺北市大安區和平東路 1 段 145 號 5 樓之 1

三、製 造 廠 商：勁達國際電子股份有限公司

四、器 材 名 稱：藍牙模組

五、廠　　牌：Raytac

六、型　　號：AN54LQ-U

七、發 射 功 率（電 場 強 度）：詳細射頻規格如備註欄

八、工 作 頻 率：詳細射頻規格如備註欄

九、審 驗 日 期：114年07月28日

十、審驗合格標籤式樣：CCAM25Y10172T0

台灣檢驗科技股份有限公司 電信設備審驗印章

十一、警語或標示要求：（器材本體、使用手冊、外包裝盒等應遵守下列標示要求）

1. 應於本體明顯處標示審驗合格標籤或符合性聲明標籤及其型號，並於包裝盒標示主管機關標章。最終產品應於本體明顯處標示非隨插即用射頻模組（組件）之審驗合格標籤及最終產品型號，並於包裝盒標示主管機關標章，始得販賣。
2. 依主管機關或相關技術規範規定於指定位置標示正體中文警語。
3. 經授權使用射頻模組(組件)之審驗合格標籤者，應於最終產品說明書及包裝盒提供充分與正確之資訊。
4. 於網際網路販賣電信管制射頻器材者，應於該網際網路網頁標示其型號及審驗合格標籤或符合性聲明標籤資訊。但最終產品得僅標示其型號及其組裝之非隨插即用射頻模組（組件）之審驗合格標籤資訊。
5. 使用手冊應標示下列資訊：
   (1) 取得審驗證明之低功率射頻器材，非經核准，公司、商號或使用者均不得擅自變更頻率、加大功率或變更原設計之特性及功能。低功率射頻器材之使用不得影響飛航安全及干擾合法通信；經發現有干擾現象時，應立即停用，並改善至無干擾時方得繼續使用。前述合法通信，指依電信管理法規定作業之無線電通信。低功率射頻器材須忍受合法通信或工業、科學及醫療用電波輻射性電機設備之干擾。

9.5. CE (EU) & RCM (Australia & New Zealand) test report

1 Mbps & 2 Mbps

AS/NZS 4268:2017 Amd 1:2021
ETSI EN 300 328 V2.2.2: 2019
TEST REPORT

Testing Laboratory 3702

Applicant:	Raytac Corp. 8F, No.788-1, Zhongzheng Rd., Zhonghe Dist., New Taipei City, 235, Taiwan
Manufacturer:	Raytac Corp. 8F, No.788-1, Zhongzheng Rd., Zhonghe Dist., New Taipei City, 235, Taiwan
Product Name:	Bluetooth Low Energy Module
Brand Name:	Raytac
Model No.:	AN54LQ
Family Model No.:	AN54LQ-P, AN54LQ-U
Model Difference:	Dimensions, Antenna type
Report Number:	TERF2502000649E2
Date of EUT Received:	February 5, 2025
Date of Test:	February 13, 2025～July 2, 2025
Issue Date:	July 21, 2025

Approved By Vito Pei
Vito Pei

We hereby certify that:

The above equipment was tested by SGS Taiwan Ltd., Central RF Lab for compliance with the requirements set forth in the European Standard ETSI EN 300 328 V2.2.2: 2019 under 2014/53/EU and Australian/New Zealand Standard AS/NZS 4268:2017 Amd 1:2021, Row 59. The results of testing in this report apply to the product system that was tested only. Other similar equipment will not necessarily produce the same results due to production tolerance and measurement uncertainties.

RF EXPOSURE REPORT

Applicant:	Raytac Corp. 8F, No.788-1, Zhongzheng Rd., Zhonghe Dist., New Taipei City, 235, Taiwan
Manufacturer:	Raytac Corp. 8F, No.788-1, Zhongzheng Rd., Zhonghe Dist., New Taipei City, 235, Taiwan
Product Name:	Bluetooth Low Energy Module
Brand Name:	Raytac
Model No.:	AN54LQ
Family Model No.:	AN54LQ-P, AN54LQ-U
Model Difference:	Dimensions, Antenna type
Date of EUT Received:	Feb. 05, 2025
Issue Date:	Jul. 21, 2025

Approved By John Yeh
John Yeh

We hereby certify that:
The above equipment was evaluated by SGS Taiwan Ltd. for compliance with the requirements set forth in the European Standard EN 62479:2010, EN 50663: 2017 and Australia/New Zealand Standard AS/NZS 2772.2:2016.

The results in this report apply to this specific product system.

Test Report issued under the responsibility of:

TEST REPORT
IEC/EN 62368-1
Audio/video, information and communication technology equipment
Part 1: Safety requirements

Report Number ..... :	TSSF2502000091L0
Date of issue ..... :	2025-07-14
Total number of pages ..... :	50
Name of Testing Laboratory preparing the Report ..... :	SGS Taiwan Ltd. Safety Laboratory
Applicant's name ..... :	Raytac Corp.
Address ..... :	8F, No.788-1, Zhongzheng Rd., Zhonghe Dist., New Taipei City, 235, Taiwan
Test specification:	
Standard ..... :	IEC 62368-1:2018 and EN IEC 62368-1:2020+A11:2020
Test procedure ..... :	Commission testing
Non-standard test method ..... :	N/A
TRF template used ..... :	IECEE OD-2020-F1:2021, Ed.1.4
Test Report Form No. ..... :	IEC62368_1F modify by SGS TW (EN)
Test Report Form(s) Originator .... :	UL(US)
Master TRF ..... :	Dated 2023-08-17

Copyright © 2021 IEC System of Conformity Assessment Schemes for Electrotechnical Equipment and Components (IECEE System). All rights reserved.

This publication may be reproduced in whole or in part for non-commercial purposes as long as the IECEE is acknowledged as copyright owner and source of the material. IECEE takes no responsibility for and will not assume liability for damages resulting from the reader's interpretation of the reproduced material due to its placement and context.

General disclaimer:

The test results presented in this report relate only to the object tested.
This report shall not be reproduced, except in full, without the written approval of the Issuing CB Testing Laboratory. The authenticity of this Test Report and its contents can be verified by contacting the NCB, responsible for this Test Report.

Test item description ..... :	Bluetooth Low Energy Module
Trade Mark(s) ..... :	Raytac
Manufacturer..... :	Raytac Corp.
	8F, No.788-1, Zhongzheng Rd., Zhonghe Dist., New Taipei City, 235, Taiwan
Model/Type reference ..... :	AN54LQ, AN54LQ-P, AN54LQ-U
Ratings ..... :	3.3Vdc

Responsible Testing Laboratory (as applicable), testing procedure and testing location(s):			
☐	**Testing Laboratory:**	SGS Taiwan Ltd., Safety Laboratory	
Testing location/ address ..... :		No. 33, Wu Chyuan Road, New Taipei Industrial Park, Wu Ku District, New Taipei City 24886, Taiwan	
Tested by (name, function, signature) ..... :		Jeffrey Liang Project handler	
Approved by (name, function, signature) .. :		Kenny Cheng Reviewer	

VERIFICATION OF COMPLIANCE

Issue Date:	Jul. 11, 2025
Applicant:	Raytac Corp.
Address:	8F, No.788-1, Zhongzheng Rd., Zhonghe Dist., New Taipei City, 235, Taiwan
Manufacturer:	Raytac Corp.
Address:	8F, No.788-1, Zhongzheng Rd., Zhonghe Dist., New Taipei City, 235, Taiwan
Product:	Bluetooth Low Energy Module
Brand Name/Trade Mark:	Raytac
Model/Type:	AN54LQ
Added Model(s):	AN54LQ-P, AN54LQ-U
Applicable Standards:	EN 301 489 –1 v2.2.3 : 2019-11 EN 301 489 –17 v3.3.1 : 2024-09 EN 55032 : 2015+A11:2020 EN IEC 61000-3-2 : 2019+A1:2021 EN 61000-3-3 : 2013+A1:2019+A2:2021+AC:2022-01 EN 61000-4-2 : 2009 EN IEC 61000-4-3 : 2020 EN 61000-4-4 : 2012 EN 61000-4-6 : 2014+AC:2015
Test Laboratory:	SGS Taiwan Ltd. Electromagnetic Compatibility Laboratory No.2, Keji 1st Rd., Guishan District, Taoyuan City, Taiwan
Test Report No.:	TMHY2502000325YE, dated on Jul. 11, 2025

Conclusion: Based upon a review of the Test Report(s), the tested sample of the product mentioned above is deemed to comply with the requirements of the above standards.

Note: This verification is only valid for the product and configuration described and in conjunction with the test report as detailed above.

Authorised Signatory:

Eddy Cheng

SGS Taiwan Ltd.
Eddy Cheng
Asst. Supervisor

Supplier's declaration of conformity

Australian Government | acma Australian Communications and Media Authority

This is the Australian Communications and Media Authority (ACMA) approved form for a declaration of conformity under the following legislative instruments:

- Radiocommunications Equipment (General) Rules 2021
- Radiocommunications Labelling (Electromagnetic Compatibility) Notice 2017.

This is a sample form for a declaration of conformity under the Telecommunications (Labelling Notice for Customer Equipment and Customer Cabling) Instrument 2025.

Instructions for completion

Do not return this form to the ACMA. This completed form must be retained by the supplier as part of the documentation required for the compliance records. However, it must be made available for inspection by the ACMA when requested.

Supplier's details (manufacturer, importer or authorised agent)

Company name (or individual)

N121 PTY LTD

ACN/ARBN

646 997 373

Street address (Australia or New Zealand)

UNIT 5, 25-31 ALEXANDRA STREET
DRUMMOYNE NSW 2047, AUSTRALIA

Product details and date of manufacture

Product description – brand name, type, current model, lot, batch or serial number (if available), software/firmware version (if applicable)

Equipment name: Bluetooth Low Energy Module
Model name: AN54LQ
Variant model name: AN54LQ-P, AN54LQ-U
Brand name: Raytac

Compliance – applicable standards and other supporting documents

Evidence of compliance with applicable standards may be demonstrated by test reports, endorsed/accredited test reports, certification/competent body statements.

Having had regard to these documents, I am satisfied the above-mentioned product complies with the requirements of the relevant ACMA standards made under the *Radiocommunications Act 1992* and/or the *Telecommunications Act 1997*.

List these documents including details of the standard title, number and, if applicable, number of the test report/endorsed test report or certification/competent body statement.

Standard	Report number
Radiocommunications Labelling (Electromagnetic Compatibility) Notice 2017 (AS/NZS CISPR 32:2015+A1:2020)	TMHY2502000326YE
Radiocommunications Equipment (General) Rules 2021	TERF2508002564E2

Declaration

I hereby declare that:

1. I am authorised to make this declaration on behalf of the Company mentioned above
2. the contents of this form are true and correct
3. the product mentioned above complies with the applicable above mentioned standards and all products supplied under this declaration will be identical to the product identified above
4. I understand that giving false or misleading information is a serious offence.

Note: It is an offence to knowingly provide false or misleading information to a Commonwealth entity or a person who is exercising powers, performing functions under, or in connection with, a law of the Commonwealth. It is an offence to knowingly provide false or misleading information or documents in compliance or purported compliance with a law of the Commonwealth. (See sections 137.1 and 137.2 of the *Criminal Code Act 1995*.)

Penalty: 12 months imprisonment

Signature of Authorised Person	Date	Print Name	Position
	August 19, 2025	Daniel	Managing Director

The *Privacy Act 1988* (Cth) (the Privacy Act) imposes obligations on the ACMA in relation to the collection, security, quality, access, use and disclosure of personal information. These obligations are detailed in the Australian Privacy Principles.

The ACMA may only collect personal information if it is reasonably necessary for, or directly related to, one or more of the ACMA's functions or activities.

The purpose of collecting the personal information in this form is to ensure the supplier is identified in the 'declaration of conformity'. If this declaration of conformity is not completed and the requested information is not provided, a compliance label cannot be applied.

Further information on the Privacy Act and the ACMA's privacy policy is available at www.acma.gov.au/privacypolicy. The privacy policy contains details about how you may access personal information about you that is held by the ACMA, and seek the correction of such information. It also explains how you may complain about a breach of the Privacy Act and how we will deal with such a complaint.

Should you have any questions in this regard, please contact the ACMA's privacy contact officer on telephone on 1800 226 667 or by email at privacy@acma.gov.au.

RSM SDoc

RADIO SPECTRUM MANAGEMENT

MINISTRY OF BUSINESS, INNOVATION & EMPLOYMENT

Supplier's Declaration of Conformity

Section 134 (1) (g) of the New Zealand Radiocommunications Act 1989

Supplier's Details:
Name: JNM NZ LIMITED
Supplier Number: E9659
New Zealand Company Number: 8308895
Address: 1 Mariner Lane Beachlands2018 New Zealand

Product Details:

Brand name (Manufacture name)	**Raytac**		
Product name (Description)	**Bluetooth Low Energy Module**	Model name	**AN54LQ**
		Variant model	**AN54LQ-P, AN54LQ-U**
Frequency	**2 402 MHz ~ 2 480 MHz**	Radiated power e.i.r.p (dBm):	**9.86 dBm**
Applicable Standards Title, Number and Edition	**AS/NZS CISPR 32:2015+A1:2020 AS/NZS 4268:2017:AMD1:2021 ETSI EN 300 328 V 2.2.2**		
Test Report Numbers	**TMHY2502000326YE TERF2508002564E2**		

I hereby declare that the product to which this Declaration of conformity relates complies with the above-mentioned standard(s), and all products supplied under this Declaration will be identical to the sample identified in this Declaration.



Daniel
Director
05 August 2025

9.6. IC Certificate (Canada)

2.4GHz wireless module



CERTIFICATE

CB TECHNICAL ACCEPTANCE CERTIFICATE
CERTIFICAT D'APPROBATION TECHNIQUE

kiwa

▶ Reg. No. NL0001

CERTIFICATION No
No. DE CERTIFICATION 8017A-AN54LQ

Issued 30 July 2025

Page 1 of 2
This certificate has ONE Annex

KIWA No. No. DE KIWA	252170402/AA/00
TEST SITE No. No. DE LABORATOIRE	4620E
ISSUED TO DÉLIVRÉ A	Raytac Corp. 8F, No.788-1, Zhongzheng Rd., Zhonghe Dist. New Taipei City 235 Taiwan
TYPE OF EQUIPMENT GENRE DE MATÉRIEL	Bluetooth device
TRADE NAME MARQUE	Raytac
MODEL (HVIN) MODELE (HVIN)	AN54LQ, AN54LQ-P, AN54LQ-U
FVIN	1
PMN	AN54LQ, AN54LQ-P, AN54LQ-U

CERTIFIED TO / CERTIFIÉ SELON LE — SPECIFICATION / CAHIER DES CHARGES: RSS-102 ISSUE 6; RSS-247 EDITION 3

ISSUED BY KIWA NEDERLAND B.V. (NL0001), RECOGNIZED CERTIFICATION BODY BY INNOVATION, SCIENCE AND ECONOMIC DEVELOPMENT CANADA, ACCORDING THE CANADIAN CERTIFICATION BODY SCHEME (REC-CB).
DÉLIVRÉ PAR KIWA NEDERLAND B.V. (NL0001), ORGANISME DE CERTIFICATION RECONNU PAR INNOVATION, SCIENCES ET DÉVELOPPEMENT ÉCONOMIQUE CANADA, SELON LE SYSTÈME D'ORGANISME DE CERTIFICATION DE CANADA (REC-CB).

I hereby attest that the subject equipment was tested and found to be in compliance with the noted specification.
J'atteste, par la présente, que le matériel a fait l'objet d'essai et a été jugé conforme à la spécification indiquée.

Kiwa Nederland B.V.
Wilmersdorf 50
Postbus 137
7300 AC Apeldoorn
The Netherlands

https://www.kiwa.com/nl/en/markets/radio-wireless-and-electrical-equipment/

Chamber of commerce
08090048

David Chen
Reviewer

George Chen
Decision maker

PRODUCTS
RvA C 002

9.7. SRRC Certificate (China)



编号： 2025-17817
Certificate No.

无线电发射设备型号核准证

Radio Transmission Equipment Type Approval Certificate

劲达国际电子股份有限公司（台湾）：

根据《中华人民共和国无线电管理条例》，经审查，下列设备准予颁发无线电发射设备型号核准证。

In accordance with the Radio Regulations of the People's Republic of China, after examination, the Radio Transmission Equipment Type Approval Certificate is granted to the following equipment.

设备名称： Equipment Name	蓝牙模块
设备型号： Equipment Type	AN54LQ-U
核准代码： CMIIT ID	25J71R80L542(M)
主要功能： Main Functions	数据传输
有效期： Validity	2030-04-03

其他事项载于附页。
Additional Items as Seen in Attachments.

中华人民共和国工业和信息化部

发证机关
Sealed by Issuing Authority

2025年 08月 15日
Year Month Date

中华人民共和国工业和信息化部统一制作
Issued by the Ministry of Industry and Information Technology of the People's Republic of China

9.8. KC Certificate (South Korea)

2.4GHz wireless module

038F-75EF-DD68-7C60

방송통신기자재등의 적합등록 필증

Registration of Broadcasting and Communication Equipments

상호 또는 성명 Trade Name or Registrant	Raytac Corporation
기자재명칭(제품명칭) Equipment Name	Bluetooth Low Energy Module
기기부호/추가 기기부호 Equipment code /Additional Equipment code	LARN8
기본모델명 Basic Model Number	AN54LQ-U
파생모델명 Series Model Number	AN54LQ, AN54LQ-P
등록번호 Registration No.	R-R-ryt-AN54LQ
제조자/제조국가 Manufacturer/Country of Origin	Raytac Corporation/대만
등록연월일 Date of Registration	2025-07-28
기타 Others	기본모델명: AN54LQ-U External Antenna Dipole Antenna Type 1) 제조자: Aristotle 모델명: HFA-02-5-F17M/10008 안테나 이득(dBi): 5.0 2) 제조자: YAGEO 모델명: ANTX1#0P111B24003 안테나 이득(dBi): 3.3 3) 제조자: YAGEO 모델명: ANTX1#0P011B24003 안테나 이득(dBi): 2.2 4) 제조자: YAGEO 모델명: ANTX1#0ETRAB24553 안테나 이득(dBi): 2.22 파생모델명: AN54LQ Internal Antenna Monopole antenna Type 1) 제조자: Raytac Corp. 안테나 이득(dBi): 1.42 파생모델명: AN54LQ-P Internal Antenna PIFA antenna Type 1) 제조자: Raytac Corp. 안테나 이득(dBi): 0.86

위 기자재는「전파법」제58조의2 제3항에 따라 등록되었음을 증명합니다.

It is verified that foregoing equipment has been registered under the Clause 3, Article 58-2 of Radio Waves Act.

2025년(Year) 08월(Month) 07일(Day)

국립전파연구원장 국립전파연구원장인

Director General of National Radio Research Agency

※ 적합등록 방송통신기자재는 반드시 **"적합성평가표시"** 를 부착하여 유통하여야 합니다.

위반시 과태료 처분 및 등록이 취소될 수 있습니다.

9.9. WPC Certificate (India)

सत्यमेव जयते

Government of India
Ministry of Communications
Department of Telecommunications
WPC Wing
Sanchar Bhawan, New Delhi-110001.

[Generation of Equipment Type Approval (ETA) through self-declaration issued under O.M. No. ETA-WPC /Policy/2018-19 dated 26 February, 2019].

THIS ETA IS ISSUED FOR A SINGLE MODEL WITH MODEL NAME AN54LQ (AN54LQ-P AN54LQ-U)

Registration No: ETA-SD-20250807326 Date: 01-09-2025

I). Details of Applicant and Parameters of Equipment:

1.	Name & Address of the first Applicant. (Indian Manufacturer/ Authorised Indian representative for foreign manufacturer)	ATOLL SOLUTIONS PRIVATE LIMITED, No. 143, First Floor, 10th Cross 1st Stage, Indiranagar Bangalore Bangalore, Bangalore Urban,KARNATAKA,560038
2.	Equipment category	Bluetooth module
3.	Make	Raytac Corporation,Taiwan
4.	Model	AN54LQ (AN54LQ-P AN54LQ-U)
5.	Frequency range(s) of Equipment	1. 2402-2480 MHz
6.	Max output power/Field strength/PSD	1. E.I.R.P. (Watts). 0.006

7.	Applicable Gazette Notification(s)	1. 1047 (E) Dated 18-10-2018	
8.	RF Test Report details:-		
	Name&Address /Country of accredited laboratory issuing the RF test report	Accreditation Certificate Reference/Number	Test Report No. and Date
	SGS Taiwan Ltd & No134, Wu Kung Road,New Taipei Industrial Park, Wuku District, New Taipei City, Taiwan	252181162/AA/00	TERF2502000650E2 & 18-07-2025

II). Terms and Conditions

(i). This certificate will not be valid in case any change in the above parameters and not conforming to the Gazette Notification mentioned in sl.no 7 above.
(ii). Use of such equipment has been exempted from licensing requirement vide Gazette Notification mentioned in sl. no. 7, on Non-interference,Non-protectionand sharing (non-exclusive) basis.
(iii). Use of such equipment in case not conforming to above notification will require a specific wireless operating license, as applicable from this Ministry.
(iv). Field units of WPC Wing reserve the right for sample check/audit carried out for the purpose of RF analysis/spectrum monitoring in view to avoid interference to other wireless users and ensure compliance of technical parameters mentioned in sl no. 5,6&7.
(v). This certificate is valid only for equipment which are exempted from import licensing requirements as per the Import Policy of DGFT and for import of such device, a self-declaration based, system generated (Saralsanchar) Import undertaking/ permission is required.
(vi). The applicant is liable for prosecution under Indian Law in case of any wrong declaration/ submission of ingenuine RF test report(s) for issue of ETA through Self-Declaration.

Note:
1. Once ETA through self-declaration is generated for a model, subsequently it may be utilized by other person(s) for import/usage purpose in India.

2. The importers of above model shall comply with other import related requirements, if any, with Customs.

This is Self-generated certificate. Hence, no signature is required. It may be downloaded/verified from the website https://saralsanchar.gov.in.

9.10. EU and UKCA Declarations of Conformity

The product complies with the applicable requirements of both the European Union and United Kingdom regulations, including the essential requirements of the following directives:

- ***Radio Equipment Directive: 2014/53/EU***
- ***RoHS Directive: 2011/65/EU Annex II and its amendment Directive (EU) 2015/863***

Conformity is demonstrated with reference to the following harmonized standards, based on test reports issued by SGS Taiwan Ltd.:

- ***EN 300 328 V2.2.2:2019***
- ***EN 301 489-1 V2.2.3 : 2019-11***
- ***EN 301 489-17 V3.3.1 : 2024-09***
- ***EN 55032 : 2015+A11:2020***
- ***EN 61000-4-2 : 2009***
- ***EN IEC 61000-4-3 : 2020***
- ***EN 61000-4-4 : 2012***
- ***EN 61000-4-6 : 2014+AC:2015***
- ***IEC 62368-1 : 2018 and BS EN IEC 62368-1 : 2020+A11:2020***

RoHS compliance reports were issued by **TÜV Rheinland Hong Kong Ltd.,** covering Directive 2011/65/EU and its amendment Directive (EU) 2015/863.

9.11. RoHS & REACH report

Please visit "Support" page of our website to download.

9.12. End-product label

It is suggested using following content adding to package or user manual or label to obey the regulation. Any rules of end-product label shall refer to each regulation for final reference.

9.12.1. FCC (USA)

The FCC statement should be included in the user manual when there is no enough space on label. Otherwise, it should be included on the label.

“This device complies with part 15 of the FCC rules. Operation is subject to the following two conditions. (1) This device may not cause harmful interference. (2) This device must accept any interference received, including interference that may cause undesired operation.”

The final end product must be labeled in a visible area with the following: **“Contain FCC ID: SH6AN54LQ”**.

9.12.2. TELEC (Japan)

When manufacturer is placing the product on the Japanese market, the product must be affixed with the following Specified Radio Equipment marking:



9.12.3. NCC (Taiwan)

根據 NCC LP0002 低功率射頻器材技術規範_章節 3.8.2：

- 取得審驗證明之低功率射頻器材，非經核准，公司、商號或使用者均不得擅自變更模組之頻率、加大功率或更改原設計之特性與功能。
- 低功率射頻器材之使用不得影響飛航安全及干擾合法通信；經發現有干擾現象時，應立即停用，並改善至無干擾時方得繼續使用。
- 低功率射頻器材須忍受合法通信或工業、科學及醫療用電波輻射性電機設備之干擾。

前述合法通信，係指依《電信管理法》規定作業之無線電通信。

此模組於取得認證後，將依規定於模組本體標示審驗合格標籤，並要求平台廠商於平台上標示。

請依下列標籤式樣自製標籤，標貼或印鑄於器材本體明顯處，始得販賣或公開陳列。

Series	標籤樣式
AN54LQ Series	CCAM25Y10170T6
AN54LQ-P Series	CCAM25Y10171T8
AN54LQ-U Series	CCAM25Y10172T0

以 AN54LQ-15 為例，平台廠商必須於平台上標示字樣「本產品內含射頻模組：ID 編號 CCAM25Y10170T6」。

「平台」定義如下：若器材組裝本案模組，消費者仍能正常使用該器材主要功能，該器材得視為平台。若器材不組裝本案模組，消費者不能正常使用該器材主要功能，該器材不能視為平台。
該類不同廠牌型號器材組裝本案審驗模組後，須分別申請型式認證。

9.12.4. IC (Canada)

The IC statement should be included in the user manual when there is no enough space on label. Otherwise, it should be included on the label.

You are cautioned that changes or modifications not expressly approved by the party responsible for compliance could void the user's authority to operate the equipment.
This device contains licence-exempt transmitter(s)/receiver(s) that comply with Innovation, Science and Economic Development Canada's licence-exempt RSS(s). Operation is subject to the following two conditions:
1. This device may not cause interference, and
2. This device must accept any interference, including interference that may cause undesired operation of the device.

L'émetteur/récepteur exempt de licence contenu dans le présent appareil est conforme aux CNR d'Innovation, Sciences et Développement économique Canada applicables aux appareils radio exempts de licence. L'exploitation est autorisée aux deux conditions suivantes :

1. l'appareil ne doit pas produire de brouillage, et
2. l'utilisateur de l'appareil doit accepter tout brouillage radioelectrique subi, meme si le brouillage est susceptible d'en compromettre le fonctionnement.

The final end product must be labeled in a visible area with the following: **"Contain IC ID: 8017A-AN54LQ"**.

9.13. Compliance and Certification

9.13.1. List of Applicable FCC Rules

This module has been tested and found to comply with the following requirements for Modular Approval.

- 47 CFR Part 15 Subpart C Intentional Radiators.

9.13.2. RF Exposure Considerations

This module has been evaluated for portable RF exposure conditions and is compliant with FCC RF exposure requirements when used in portable configurations. The module is approved for use without a minimum separation distance from the user's body.

Host product manufacturers integrating this module must ensure that their final host product maintains the portable use conditions as tested and documented in the RF exposure compliance reports referenced in the RF exposure exhibit.

Configuration with multiple transmitters in the same host, routine evaluation or SAR testing for the simultaneous transmission of the co-located transmitters according to KDB 447498 is required. The potable host product shall be evaluated for ensuring to continue compliance FCC rule part 2.1093 & part 1.1310 by C2PC. The additional guidance for the portable host products is provided in KDB Publication 996369 D02 and D04.

For the host product is not installed according to this guide, the module certification will be invalid, and a new grant certification will be required for the host product.

End-user documentation shall include the RF exposure information provided below.

RF Exposure Statement:

This equipment complies with FCC radiation exposure limits set forth for an uncontrolled environment. This transmitter must not be co-located or operating in conjunction with any other antenna or transmitter. The device has been evaluated for portable operation without separation distance from the user and meets the FCC RF exposure requirements for such use.

9.13.3. Antennas

This radio transmitter has been approved by Federal Communications Commission and Innovation, Science and Economic Development Canada to operate with the antenna types listed below, with the maximum permissible gain indicated. Antenna types not included in this list that have a gain greater than the maximum gain indicated for any type listed are strictly prohibited for use with this device.

Cet émetteur radio a été approuvé par la Commission fédérale des communications et Innovation, Sciences et Développement économique Canada pour fonctionner avec les types d'antennes énumérés ci-dessous, avec le gain maximal autorisé indiqué. Les types d'antennes non mentionnés dans cette liste dont le gain est supérieur au gain maximal indiqué pour l'un des types énumérés sont strictement interdits avec cet appareil.

On board antenna

Antenna Type	Supplier	Antenna Part No.	Freq. (MHz)	Peak Antenna Gain (dBi)
Monopole	Raytac	AN54LQ	2400~2500	1.42
PIFA	Raytac	AN54LQ-P	2400~2500	0.06

External antenna

Antenna Type	Supplier	Antenna Part No.	Freq. (MHz)	Peak Antenna Gain (dBi)
Dipole	Aristotle	RFA-02-5-F17H170100B	2400~2500	5
Dipole	YAGEO	ANTX100P111B24003	2400~2500	3.3
Dipole	YAGEO	ANTX100P011B24003	2400~2500	2.2
Dipole	Pulse	ANTX100ETHAB24553	2400~2500	2.22

9.13.4. Information on Test Modes and Additional Testing Requirements

The module can be configured to continuously transmit on a specific frequency with a fixed modulation pattern. This allows evaluation of radiated emissions and spurious emissions in a controlled condition.

These test modes are intended for compliance testing only and must not be enabled during normal operation of the final product.

For more detailed information, please contact the grantee for assistance with test modes needed for module/host compliance test requirements.

9.13.5. Additional Testing, Part 15 Subpart B Disclaimer

The modular transmitter is only FCC authorized for the specific rule parts (i.e., FCC transmitter rules) listed on the grant, and that the host product manufacturer is responsible for compliance to any other FCC rules that apply to the host not covered by the modular transmitter grant of certification.

The final host product still requires Part 15 Subpart B compliance testing with the modular transmitter installed.

9.13.6. Note EMI Considerations

Note that a host manufacture is recommended to use KDB996369 D04 Module Integration Guide recommending as "best practice" RF design engineering testing and evaluation in case non-linear interactions generate additional non-compliant limits due to module placement to host components or properties.

For standalone mode, reference the guidance in KDB996369 D04 Module Integration Guide and for simultaneous mode; see KDB996369 D02 Module Q&A Question 12, which permits the host manufacturer to confirm compliance.

9.13.7. How to Make Changes

You are cautioned that changes or modifications not expressly approved by the party responsible for compliance could void the user's authority to operate the equipment. Only Grantees are permitted to make permissive changes, if the module will be used differently than granted conditions, please contact us to ensure modifications will not affect compliance.

RAYTAC

10. Notes and Cautions

To ensure proper integration and long-term reliability of this RF module, the following regulatory and technical considerations must be observed:

The OEM integrator must not provide instructions to the end user regarding how to install or remove this RF module in the user manual of the final product that integrates this module. The end user manual shall include all required regulatory information and warnings as shown in the official user manual.

This module is not designed for lifetime use. Like general electronic products, it may degrade after continuous usage over the years. To ensure optimal performance and longevity, please observe the following precautions:

- Follow the guidelines of this document while designing circuit/end-product. Any discrepancy of core Bluetooth technology and technical specification of IC should refer to definition of Bluetooth Organization and Nordic Semiconductor as final reference.

- Do not supply voltage that is not within range of specification.

- Eliminate static electricity at any cost when working with the module as it may cause damage. It is highly recommended adding anti-ESD components to circuit design to prevent damage from real-life ESD events. Anti-ESD methods can be also applied in mechanical design.

- Do not expose modules under direct sunlight for long duration. Modules should be kept away from humid and salty air conditions, and any corrosive gasses or substances. Store it within -40℃ to +125℃ before and after installation.

- Avoid any physical shock, intense stress to the module or its surface.

- Do not wash the module. No-Clean Paste is used in production. Washing it will oxidize the metal shield and have chemistry reaction with No-Clean Paste. Functions of the module are not guaranteed if it has been washed.

The module is not suitable for life support device or system and not allowed to be used in destructive device or systems in any direct or indirect ways. The customer agrees to indemnify Raytac for any losses when applying modules in applications such as the ones described above.

11. Useful links

- Nordic Infocenter: https://docs.nordicsemi.com/
  All the necessary technical files and software development kits of Nordic's chip are on this website.

- Nordic DevZone: https://devzone.nordicsemi.com/questions/
  A highly recommended website for firmware developer. Interact with other developers and Nordic's employees will help with your questions. The site also includes tutorials in detail to help you get started.

- Official page of nRF54L15 : https://www.nordicsemi.com/Products/nRF54L15
  A brief introduction to nRF54L15 and download links for Nordic's developing software and SoftDevices.

RAYTAC

Full list of Raytac's Wi-Fi modules

● AN7002Q series (QFN package IC)

Series	Nordic Solution	Raytac No.	IC Ver.	Antenna	RAM*	Flash Memory*
AN7002Q	nRF7002	AN7002Q	1	Chip Antenna	N/A	N/A
		AN7002Q-P	1	PCB Antenna	N/A	N/A
		AN7002Q-U	1	u.FL Connector	N/A	N/A

∗RAM and Flash Memory depend on the AN7002Q series module's host MCU.

● AN7002Q + MDBT53 series

Series	Nordic Solution	Raytac No.	IC Ver.	Antenna	RAM	Flash Memory
AN7002Q + MDBT53	nRF7002 + nRF5340	AN02C53C	1	Chip Antenna	512 kB	1 MB
		AN02P53P	1	PCB Antenna	512 kB	1 MB
		AN02U53U	1	u.FL Connector	512 kB	1 MB

Full list of Raytac's Bluetooth modules

● AN54LM series (WLCSP package IC)

Series	Nordic Solution	Raytac No.	IC Ver.	Antenna	RAM	NVM	Axon NPU
AN54LM	nRF54LM20A	AN54LM-20A	1	Chip Antenna	512 KB	2036 KB	No
	nRF54LM20B	AN54LM-20B	1				Yes
AN54LM-P	nRF54LM20A	AN54LM-P20A	1	PCB Antenna	512 KB	2036 KB	No
	nRF54LM20B	AN54LM-P20B	1				Yes
AN54LM-U	nRF54LM20A	AN54LM-U20A	1	u.FL Connector	512 KB	2036 KB	No
	nRF54LM20B	AN54LM-U20B	1				Yes

● AN54LMQ series (QFN package IC)

Series	Nordic Solution	Raytac No.	IC Ver.	Antenna	RAM	NVM	Axon NPU
AN54LMQ	nRF54LM20A	AN54LMQ-20A	1	Chip Antenna	512 KB	2036 KB	No
	nRF54LM20B	AN54LMQ-20B	1				Yes
AN54LMQ-P	nRF54LM20A	AN54LMQ-P20A	1	PCB Antenna	512 KB	2036 KB	No
	nRF54LM20B	AN54LMQ-P20B	1				Yes
AN54LMQ-U	nRF54LM20A	AN54LMQ-U20A	1	u.FL Connector	512 KB	2036 KB	No
	nRF54LM20B	AN54LMQ-U20B	1				Yes

AN54LQ series (QFN package IC)

Series	Nordic Solution	Raytac No.	IC Ver.	Antenna	RAM	NVM
AN54LQ	nRF54L15	AN54LQ-15	1	Chip Antenna	256 kB	1524 KB
	nRF54L10	AN54LQ-10	1		192 kB	1012 KB
	nRF54L05	AN54LQ-05	1		96 kB	500 KB
AN54LQ-P	nRF54L15	AN54LQ-P15	1	PCB Antenna	256 kB	1524 KB
	nRF54L10	AN54LQ-P10	1		192 kB	1012 KB
	nRF54L05	AN54LQ-P05	1		96 kB	500 KB
AN54LQ-U	nRF54L15	AN54LQ-U15	1	u.FL Connector	256 kB	1524 KB
	nRF54L10	AN54LQ-U10	1		192 kB	1012 KB
	nRF54L05	AN54LQ-U05	1		96 kB	500 KB

AN54LV series (WLCSP package IC)

Series	Nordic Solution	Raytac No.	IC Ver.	Antenna	RAM	NVM
AN54LV	nRF54L15	AN54LV-15	1	Chip Antenna	256 kB	1524 KB
AN54LV-P		AN54LV-P15	1	PCB Antenna		
AN54LV-U		AN54LV-U15	1	u.FL Connector		
AN54LV-K		AN54LV-K15	1	Pin Antenna		

MDBT53 series (WLCSP package IC)

Series	Nordic Solution	Raytac No.	IC Ver.	Antenna	RAM	Flash Memory
MDBT53	nRF5340	MDBT53-1M	1	Chip Antenna	512 kB	1 MB
MDBT53-P	nRF5340	MDBT53-P1M	1	PCB Antenna	512 kB	1 MB
MDBT53-U	nRF5340	MDBT53-U1M	1	u.FL Connector	512 kB	1 MB

MDBT53V series (WLCSP package IC)

Series	Nordic Solution	Raytac No.	IC Ver.	Antenna	RAM	Flash Memory
MDBT53V	nRF5340	MDBT53V-1M	1	Chip Antenna	512 kB	1 MB
MDBT53V-P	nRF5340	MDBT53V-P1M	1	PCB Antenna	512 kB	1 MB

MDBT50 series (QFN package IC)

Series	Nordic Solution	Raytac No.	IC Ver.	Antenna	RAM	Flash Memory
MDBT50	nRF52820	MDBT50-256R	1	Chip Antenna	32 kB	256 kB
	nRF52833	MDBT50-512K	1		128 kB	512 kB
MDBT50-P	nRF52820	MDBT50-P256R	1	PCB Antenna	32 kB	256 kB
	nRF52833	MDBT50-P512K	1		128 kB	512 kB

MDBT50Q series (aQFN package IC)

Series	Nordic Solution	Raytac No.	IC Ver.	Antenna	RAM	Flash Memory
MDBT50Q	nRF52840	MDBT50Q-1MEN	3	Chip Antenna	256 kB	1 MB
	nRF52840	MDBT50Q-1MV2	2			
	nRF52833	MDBT50Q-512K	1		128 kB	512 kB
MDBT50Q-P	nRF52840	MDBT50Q-P1MEN	3	PCB Antenna	256 kB	1 MB
	nRF52840	MDBT50Q-P1MV2	2			
	nRF52833	MDBT50Q-P512K	1		128 kB	512 kB
MDBT50Q-U	nRF52840	MDBT50Q-U1MEN	3	u.FL Connector	256 kB	1 MB
	nRF52840	MDBT50Q-U1MV2	2			
	nRF52833	MDBT50Q-U512K	1		128 kB	512 kB
Dongle	nRF52840	MDBT50Q-RX	1, 2	PCB Antenna	256 kB	1 MB
		MDBT50Q-CX-40	1			
	nRF52833	MDBT50Q-CX-33	1		128 kB	512 kB

MDBT42T series (WLCSP package IC)

Series	Nordic Solution	Raytac No.	IC Ver.	Antenna	RAM	Flash Memory
MDBT42T	nRF52805	MDBT42T-192K	1	Chip Antenna	24 kB	192 kB
MDBT42T-P		MDBT42T-P192K		PCB Antenna		

MDBT42TV series (WLCSP package IC)

Series	Nordic Solution	Raytac No.	IC Ver.	Antenna	RAM	Flash Memory
MDBT42TV	nRF52805	MDBT42TV-192K	1	Chip Antenna	24 kB	192 kB
MDBT42TV-P		MDBT42TV-P192K		PCB Antenna		

MDBT42 series (WLCSP package IC)

Series	Nordic Solution	Raytac No.	IC Ver.	Antenna	RAM	Flash Memory
MDBT42	nRF52832	MDBT42-512KV2	2	Chip Antenna	64 kB	512 kB
MDBT42-P		MDBT42-P512KV2		PCB Antenna		

MDBT42V series (WLCSP package IC)

Series	Nordic Solution	Raytac No.	IC Ver.	Antenna	RAM	Flash Memory
MDBT42V	nRF52832	MDBT42V-512KV2	2	Chip Antenna	64 kB	512 kB
MDBT42V-P		MDBT42V-P512KV2		PCB Antenna		

MDBT42Q series (QFN package IC)

Series	Nordic Solution	Raytac No.	IC Ver.	Antenna	RAM	Flash Memory
MDBT42Q	nRF52832	MDBT42Q-512KEN	3	Chip Antenna	64 kB	512 kB
	nRF52832	MDBT42Q-512KV2	2			
	nRF52810	MDBT42Q-192KV2	2		24 kB	192 kB
	nRF52811	MDBT42Q-192KL	1			
MDBT42Q-P	nRF52832	MDBT42Q-P512KEN	3	PCB Antenna	64 kB	512 kB
	nRF52832	MDBT42Q-P512KV2	2			
	nRF52810	MDBT42Q-P192KV2	2		24 kB	192 kB
	nRF52811	MDBT42Q-P192KL	1			
MDBT42Q-U	nRF52832	MDBT42Q-U512KEN	3	u.FL Connector	64 kB	512 kB
	nRF52832	MDBT42Q-U512KV2	2			

MDBT40 series

Series	Nordic Solution	Raytac No.	IC Ver.	Antenna	RAM	Flash Memory
MDBT40	nRF51822	MDBT40-256V3	3	Chip Antenna	16 kB	256 kB
		MDBT40-256RV3			32 kB	256 kB
MDBT40-P	nRF51822	MDBT40-P256V3	3	PCB Antenna	16 kB	256 kB
		MDBT40-P256RV3			32 kB	256 kB

Release Note

- 2025/11/05 Version 1.0: 1st release.

- 2026/06/12 Version 1.1:
  (1) Corrected text errors in Section 1: Overall Introduction.
  (2) Removed Note content from drawing in Section 2.1: PCB dimensions & pin Indication.
  (3) Updated drawing to add reference via patterns and "AN54LQ-15 GND pouring" text in Section 2.3: RF layout suggestion.
  (4) Added APET material note to Tray packaging in Section 4: Shipment packaging information.
  (5) Added GPIO Electrical specification in Chapter 5.3: Electrical Specifications.
  (6) Updated block diagram in Chapter 6: Block Diagram.
  (7) Updated SGS test report references in Section 9.10 and updated user manual instructions in Section 9.13.7: How to Make Changes.
  (8) Updated section content in Section 9.12.4: IC (Canada).
  (9) Updated Raytac's BLE module list to include the AN54LV series modules.

- 2026/09/09 Version 1.2:
  (1) Updated diagram annotations in Section 5.3: RF Layout Suggestion (aka Keep-Out Area).
  (2) Added AN7002Q+MDBT53 series in Full List of Raytac’s Wi-Fi Modules.
  (3) Added AN54LM series and AN54LMQ series in Full List of Raytac’s Bluetooth Modules.